

ENGINEERING DEPARTMENT
Town of Poughkeepsie

PETER D. SETARO, P. E.

Town Engineer

DONALD A. BEER

Associate Town Engineer

SEAN CRIMMINS

Assistant Town Engineer

PETER HOBDDAY

Assistant Town Engineer

ONE OVEROCKER ROAD
POUGHKEEPSIE, NY 12603

TEL # (845) 790-4736

TEL # (845) 790-4748

TEL # (845) 790-4747

**TOWN OF POUGHKEEPSIE
ARLINGTON WASTEWATER TREATMENT PLANT TUNNEL
REPAIRS TO SUPPORTS FOR PIPES
POUGHKEEPSIE, NEW YORK**

CONTRACT 2017-06

Addendum No. 1

October 30, 2017

Page 1 of 5

Some questions were asked by prospective bidders at the pre-bid meeting on October 30. The following responses and information are provided.

Q Are there special steel requirements?

A The contractor shall provide steel in accordance with the specifications. There is no "Buy America" requirement.

Q What is the cost estimate?

A The similar project was bid earlier for \$223,228 but not awarded due to the overlapping work with other contractors and the irresolvable conflicts.

Q Can the repairs be simplified?

A The general scope assumes that only the rusted and failed steel parts will be replaced. However, the contractor has the option to replace in kind any support by constructing an adjacent "sister" replacement. Also, see the attached revised base plate details.

Q Is grout required under the base plates?

A The design assumes a smooth concrete floor. If the surface texture does not provide uniform bearing for a new base plate, the plate shall be set in a bed of non-shrink grout.

CONTRACT 2017-06

Addendum No. 1

October 30, 2017

Page 2 of 5

Q What steel shall be painted?

A All new steel shall be primer coated and painted, and all adjacent areas of existing steel where the paint was disturbed shall be primer coated and painted.

Q Is there a change in scope for the painting work?

A The contractor shall note that this addendum changes the scope of the painting required. All repairs shall be fully primer coated and painted as part of the base bid. A new Add Alternate is shown on the Bid Sheet, and the scope is to primer coat and paint all steel frames listed on the Work Schedule, regardless of the extent of repairs including no repairs, to provide a uniform appearance for the steel supports.

End of Addendum No. 1 text; attached drawing is page 3; attached Bid Sheets are pages 4 and 5.