

ENGINEERING DEPARTMENT
Town of Poughkeepsie

PETER D. SETARO, P. E.

Town Engineer

DONALD A. BEER

Associate Town Engineer

ROBERT E. BOZEK

Assistant Town Engineer

KYLE SOUTHERN

Assistant Town Engineer

ONE OVEROCKER ROAD
POUGHKEEPSIE, NY 12603

TEL # (845) 790-4736

TEL # (845) 790-4747

TEL # (845) 790-4748

**TOWN OF POUGHKEEPSIE
HAGAN TOWN PUMP STATION
ABANDONMENT AND REPLACEMENT
POUGHKEEPSIE, NEW YORK**

CONTRACT 2020-01

Addendum No. 2

March 4, 2020

Page 1 of 2

This addendum is issued following the pre-bid meeting on February 17, 2020 at the site and further follow up questions.

1. Is there a construction estimate of cost for the project?
 - a. The construction estimate for the project is in the range of \$400,000 to \$450,000, not to exceed \$500,000.
2. What are the required M/WBE percentages for this contract?
 - a. Please refer to Section 00415 EFC FORMS which states: "The specific requirements are listed in the specifications and include a combined M/WBE goal of 23% of the contract, and EEO goals of 6.4% minority and 6.9% women".
 - b. Please also refer to Section 00817 HMGP Supplementary Conditions; Exhibit E; Sub Section Civil Rights and Diversity Provisions; item 19 which states: "Contractor will use its best efforts to afford small businesses, minority business enterprises, and women's business enterprises the maximum practicable opportunity to participate in the performance of the contract."
3. What is the NYS EFC SRF Number?
 - a. C3-7323-05-00.
4. Who is the Smith and Loveless Rep for this area/contract?
 - a. Please contact Michael Whelan with Hydra-Numatic Sales Company at (973) 492-0181 ext 104 or mwhelan@hnscompany.com

5. Are there any trees that need to be removed?
 - a. Yes, please refer to the DP-1 Demo Plan in the plan set. 3 trees will need to be removed, 1 shown near the front of the lot was recently removed after falling in a storm.

6. Who is responsible for any potential sanitary sewer bypass pumping when installing the Dog House MHs?
 - a. The Town Sewer Department has agreed to provide temporary bypass pumping that will be required for tying in the Dog House MHs under the following terms:
 - i. A minimum of 15 working days notice will be required prior to bypassing.
 - ii. Bypassing should be set up during low flow periods agreed upon by the Town Sewer Superintendent.
 - iii. Bypass pumping must be complete during regular working hours of the Town Sewer Department, 7:00 AM to 3:30 PM. Overnight pumping will not be provided by the Town.
 - iv. Ample preparations should be made to complete all work possible prior to bypassing to limit the amount of time required for pumping.

7. Will the Contractor be responsible for disposal of old equipment?
 - a. The Town Sewer Department will take any reusable or salvageable equipment, ie; valves, pumps, control panel, disconnect switches, etc. The contractor will be responsible for disposal of any debris, piping, fittings, etc.

8. Who is responsible for removal of the generator?
 - a. The Contractor will be responsible to disconnect and lift the generator and fuel tank from the ground. The Town Sewer Department will drain the fuel tank prior to removal and will provide a trailer for the generator and fuel tank to be loaded onto (by the Contractor) for relocation to another Town site.

9. There is conflicting information for the existing flushing hydrant, is this to be removed or stay in place?
 - a. The flushing hydrant no longer works and should be removed as part of the contract. It is understood that this line was previously disconnected and is no longer live. The Contractor will only be responsible for removal of the hydrant, not the buried service line.

10. Are there any soil borings for the site?
 - a. Please review Addendum 1 in the project specifications.